

NOTES:

Refer to other Standard Details for remaining parts of the manhole. Also refer to the Contract Specifications. At no time are these details to supercede, but to work in conjunction with other standards and specifications.


Manhole risers and cones shall meet the requirements of ASTM C478 except that a wall thickness of 5" will be required. Length of each riser shall be a multiple of 16". Length of cone shall be 2'-8" minimum. Two lift holes are permitted in each unit, and must be filled with non-shrink mortar after setting manhole.

"Drycast" manholes are not allowed. Manhole must be "wetcast".

Sanitary manholes are to be built without steps. If steps are installed, they shall be cut flush and patched over smooth with non-shrink mortar.

Seal the inside of precast joints with non-shrink mortar with a smooth finish.

Concentric corbel is optional.



CITY OF HOLLAND, MICHIGAN
Holland Board of Public Works
 Water & Wastewater Department
 625 Hastings Ave., Holland, MI 49423
 Phone: (616) 355-1643 - Fax: (616) 355-1560
 Director: John Van Uffelen, P.E.

SANITARY MH FOR SEWERS 8" TO 21"
STANDARD DETAIL

DRAWN BY	SCALE	DATE
DJS	NONE	02-28-2005
APPROVED BY	SHEET	DWG FILE
DLW	SAN-2	Sanitary MH 8-21.dwg